

BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P. Bengaluru - 64


No:EE/YNK-D/E-PMT/08/2016-17 Dated: 4-03-2017

APPROVED TENDER SCHEDULE -'B'

Item No: 30

Name of Work:- Improvements to roads and drain at surya vamshi layout in ward No- 02 of yelahanka Sub Division

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri G VENKATE GOWDA	
				Rate	Rate in Words
1	Removing B.S. slab of Drain and stacking.(P No.25 / I N 5.32)	Sqm	630.00 ✓	60.00 ✓	Rupees sixty only
2	KSRRB 300 - Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH Chapter 3 (P.142/I.19.1)	Cum	172.08 ✓	80.00 ✓	Rupees eighty only
3	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No 17.1)	Cum	172.08 ✓	90.00 ✓	Rupees ninety only
4	Refixing stone slabs of drains and pointing in C.M.(1:3)(P.No.25/I.No.5.33)	Sqm	441.00 ✓	70.00 ✓	Rupees seventy only
5	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete 7.5 cms thick (Page No.25, Item No. 5.31.1)	Sqm	169.00 ✓	600.00 ✓	Rupees six thousand only
6	KSRRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No.KBS 4.1, 4.2 (P.12/I.4.3)	Cum	17.84 ✓	4999.30 ✓	Rupees four thousand nine hundred ninety nine and paise thirty only


Executive Engineer
Yelahanka Division
Yelahanka Zone

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri G VENKATE GOWDA	
				Rate	Rate in Words
7	KSRB 5-11 : Providing and constructing load bearing wall with cement concrete cavities blocks (hollow blocks) of proportion 1:1.5:3 blocks of size 40x20x20cms.(lxbxh) strength not less than 3.5 Newton per sqmm with cement mortar 1:4 conforming to I.S.2185 of 1967 having not less than 40mm.shell thickness with two or more large cavities and having solid material between including cost of materials, labour charges, scaffoldings, curing complete as per specifications. KBS No.5.4 (P.24 / I.N 5.25)	Sqm	356.80	950.00	Rupees nine hundred fifty only
8	KSRB 15.1.1: Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.(Page No.113/Item No. 15.1)	Sqm	356.80	100.00	Rupees one hundred only
9	KSRB 4-1.7 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs with 20mm and down size graded granite metal coarse aggregate @ 0.84cum and fine aggregate @ 0.56 cum machine mixed concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification. No. KBS 4.1,4.2.(P No. 13 / Item No.4.7)	Cum	17.84	5091.00	Rupees five thousand ninety one only
10	Providing and fixing RCC precast Slabs of 0.10 m thick of CC 1:2:4 with 20 mm and down size graded granite metal , machine mixed , including cost of all material , labour , HOM of Machinery , curing complete	Sqm	401.40	2018.00	Rupees two thousand eighteen only
11	5.29(b)Providing and fixing pre cast solid cement concrete kerb stones made out of No.272.21 C.C 1:2:4 with top and bottom width 114 and 165mm repectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork curing, including, cost of all materials, labour hire charges of machinery, loading unloading, lead and lift, transportation etc, complete (P.No.25 /It.No.5.30)	Sqm	990.00	330.00	Rupees three hundred thirty only
12	KSRB 15-19.2 :Providing and applying ready mix priming coat over concrete/masonry/asbestos cement sheet/plastered surfaces including preparing the surface after thoroughly cleaning of oil,grease,dirt and other foreign matter and sand papering including cost of materials, labour, complete as per specifications. (Page no.121 / It no.15.80)	Sqm	178.40	27.00	Rupees twenty seven only
13	KSRB 800-1.Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. (Page No.182 & Item No.24.1)	Sqm	178.40	63.00	Rupees sixty three only